



Modular building consisting of:
 cabins: 1x20'
 internal height: 2340 mm
 colour: R: RAL 7035 P:RAL 7035

General

Internal finish: white
 ID steel sheet version (complete)

Electrics

Electric GB (230V/32A/3-poles)
 flexible cable system

Floor assembly

Forklift pocket distance: 2050mm
 Floor insulation: 60 mm mineral wool
 Cement-bound chipboard floor
 Surestep flooring - pulled up on sides

Roof assembly

Roof insulation: 100 mm mineral wool

panels

PU-panels (60 mm)

window

Gas filled window

Sanitary

flushing cistern with water saving device
 Pressure reduction valve incl. backwash filter (GB)

Miscellaneous

X...H=1700 mm über FOK
 X...Berührlose WT-Armatur

20pu-3plus1-7035-led.dwg